



Simon L. Greenberg, MCE, President and CEO  
Board of Trustees  
Chancellor Joel I. Klein, Chairman  
Stanley E. Grapson, Trustee  
Lillian Baruch-Paul, Trustee  
Architecture & Engineering  
E. Bruce Barrett, P.A., Vice President  
Ben R. Albert, P.E., Director of Design Studio 1  
Stanley Dapkin, Director of Design Studio 2  
Pablo A. Gomez, P.E., Director of Design Studio 3  
George D. Roussay, P.E., Director of Technical Standards & Support Studio  
Beatrix Ocasio, Director of Operations Support

**GoshowArchitects**  
34 West 25th Street, 16th Floor, New York, NY 10001  
P: 212.623.7575 / F: 212.252.7460

**LAWLESS & MANGIONE**  
ARCHITECTS & ENGINEERS  
400 NORTH BROADWAY, YORKTOWN, NY 10595  
609.438.9000  
609.438.9001  
FAX 609.432.4881  
WSP CANTOR SEINUK  
STRUCTURAL ENGINEERS  
228 EAST 42ND STREET, NEW YORK, NEW YORK 10017  
TEL: 212-687-2488 FAX: 646-487-5801 WWW.CANTORSEINUK.COM

DUCT SYMBOLS



EXHAUST DUCT SECTION OR FLUE

ABBREVIATIONS

A.D. ACCESS DOOR  
B.O. SHEET METAL BLANK OFF  
C.F.M. CUBIC FEET PER MINUTE  
E.F. EXHAUST FAN  
EX. EXHAUST  
EL. ELEVATION

GENERAL NOTES (MECHANICAL)

- ALL WORK SHALL COMPLY WITH AND BE INSTALLED IN ACCORDANCE WITH NEW YORK CITY BUILDING CODE AND CODES HAVING JURISDICTION OVER THE WORK FOR A COMPLETE FUNCTIONING SYSTEM.
- CONTRACTOR SHALL VERIFY EXACT LOCATION OF ALL EXISTING EQUIPMENT AND PIPING IN FIELD PRIOR TO BID. FABRICATION AND INSTALLATION OF ANY NEW WORK.
- DUCTWORK IS SHOWN DIAGRAMMATICALLY. EXACT ROUTING OF NEW DUCTWORK SHALL BE DETERMINED IN FIELD.
- THE WORDS PROVIDE OR INSTALL, SINGLY OR IN COMBINATION SHALL MEAN FURNISH AND INSTALL.
- THE CONTRACTOR SHALL PROVIDE ALL CUTTING AND PATCHING AS REQUIRED FOR THE INSTALLATION OF HIS WORK.
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF HIS WORK AND NEWLY INSTALLED OR INCLUDING PROTECTION OF BUILDING OCCUPANTS, PUBLIC AND PERSONNEL. PROVIDE APPROPRIATE BARRIERS AND SAFETY GUARD RAILS AS REQUIRED.
- WHERE WELDING OR OPEN FLAME IS USED FOR CUTTING, SOLDERING, ETC., CONTRACTOR SHALL PROVIDE FIRE EXTINGUISHERS IN PROXIMITY OF WORK AREA.
- ALL TRADES RELATED TO THE INSTALLATION OF THIS PROJECT.
- THE CONTRACTOR SHALL TURN OVER TO THE OWNER AT THE COMPLETION OF ALL WORK, THREE (3) COPIES OF OPERATING, MAINTENANCE AND INSTRUCTION MANUALS WHICH SHALL INCLUDE ALL EQUIPMENT BROCHURES, DUCT AND WIRING DIAGRAMS, DRAWINGS, TEMPERATURE CONTROLS, AND START-UP AND SHUTDOWN PROCEDURES OF ALL NEW EQUIPMENT INSTALLED.
- THE CONTRACTOR SHALL FEE FOR AND SECURE ALL PERMITS AND PAY ALL FEES REQUIRED FOR THE INSTALLATION OF HIS WORK.
- THE CONTRACTOR SHALL GUARANTEE ALL MATERIAL AND WORK INSTALLED BY HIM TO BE FREE FROM DEFECTS IN WORKMANSHIP FOR A PERIOD OF ONE (1) YEAR AFTER ACCEPTANCE OF THE INSTALLATION BY THE ENGINEER AND OWNER. THE CONTRACTOR SHALL SUBMIT A WRITTEN STATEMENT STATING SAME TO THE OWNER.
- ALL WORK SHALL BE PERFORMED BY LICENSED CONTRACTORS IN THE TRADE HAVING JURISDICTION.
- ANY DEVIATION OR CHANGE IN DESIGN SHALL NOT BE MADE WITHOUT WRITTEN APPROVAL OF THE ENGINEER OR OWNER.
- THIS CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL EQUIPMENT AND MATERIALS INCLUDING CONTROL WIRING DIAGRAMS TO THE ENGINEER FOR APPROVAL PRIOR TO FABRICATION AND INSTALLATION OF NEW WORK. SHOP DRAWINGS SHALL INDICATE STRUCTURAL MEMBERS, WALLS, FLOORS, PARTITIONS, AND EXISTING MECHANICAL SYSTEMS. WORK IS TO BE INSTALLED. ANY DEVIATION IN DESIGN SHALL NOT BE MADE WITHOUT WRITTEN APPROVAL OF THE ENGINEER OR OWNER.

HVAC NOTES


- PROVIDE SLEEVES FOR ALL DUCTS AND PIPING PASSING THROUGH PARTITIONS, FLOORS OR MASONRY WALLS. PACK SLEEVE AROUND DUCT WITH THERMOFIBER OR APPROVED FIRE RATED MATERIAL. SLEEVES SHALL BE 1/8 GAGE GALVANIZED SHEET STEEL. SEAL ALL SLEEVES WETHERTIGHT THROUGH EXTERIOR WALLS.
- SUSPEND AND SUPPORT ALL NEW DUCTWORK AND EQUIPMENT FROM BUILDING STRUCTURE ONLY.
- DUCTWORK SHALL BE FABRICATED AND INSTALLED ACCORDING TO LOCAL CODE & SMACNA LOW PRESSURE FLEXIBLE AND METAL DUCT STANDARDS LATEST EDITION. PROVIDE BUTTERFLY TYPE VOLUME DAMPERS WITH LOCKING QUADRANT AS INDICATED ON THE PLANS. DUCT SHALL BE 10 GA. BLACK IRON.
- PROVIDE ALL SUPPORT STEEL AS REQUIRED FOR DUCTWORK.
- THIS CONTRACTOR SHALL HIRE AN INDEPENDENT BALANCING CONTRACTOR WHO IS CERTIFIED BY AABC OR NEBB TO PERFORM AIR BALANCING WORK. THREE (3) COPIES OF BALANCING REPORT TO BE SUBMITTED TO THE ARCHITECT/ENGINEER AND OWNER FOR APPROVAL.
- ALL WIRING OF MECHANICAL EQUIPMENT, ETC. SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR UNDER THE SUPERVISION OF THE HVAC CONTRACTOR.
- ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MFRS RECOMMENDATIONS.

100% QC SUBMISSION

MECHANICAL SYMBOLS, ABBREVIATIONS,  
NOTES, AND SCHEDULES

Drawing No.:  
**H001**

Sheets in Contract:  
16 of 18



SCA Design Manager  
Project Architect  
Designed by:  
Drawn by:  
Checked by:  
QA Project No.:  
Design No.:  
D# 012259  
K 189  
P.S. 189 LINCOLN TERRACE  
PARAPETS, EXTERIOR MASONRY  
Address:  
1100 EAST NEW YORK AVE  
BROOKLYN, NY 11212

Drawing Title: